



Test Report: MSP-100-15

100W Single Output with PFC Function

■ DESIGN VERIFY TEST

Output Function Test

Input Function Test

Protection Function Test

Control Function Test

Component Stress Test

■ SAFETY & E.M.C. TEST

Safety Test

E.M.C. Test

■ RELIABILITY TEST

ENVIRONMENT TEST

DESIGN VERIFY TEST
OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	RIPPLE & NOISE	V1 : 150 mVp-p (Max)	I/P : 230VAC O/P : FULL LOAD Ta : 25°C	V1 : 104 mVp-p (Max)	P
2	OUTPUT VOLTAGE ADJUST RANGE	CH1 : 14.25V ~ 18 V	I/P : 230 VAC I/P : 115 VAC O/P : MIN LOAD Ta : 25°C	13.074 V ~ 18.541 V / 230 VAC 13.075 V ~ 18.541 V / 115 VAC	P
3	OUTPUT VOLTAGE TOLERANCE	V1 : 1.5 % - -1.5 % (Max)	I/P : 100 VAC / 264 VAC O/P : FULL / MIN LOAD Ta : 25°C	V1 : 0.45 % ~ -0.45 %	P
4	LINE REGULATION	V1 : 0.3 % - -0.3 % (Max)	I/P : VAC ~ 264 VAC O/P : FULL LOAD Ta : 25°C	V1 : 0 % ~ 0 %	P
5	LOAD REGULATION	V1 : 0.8 % - -0.8 % (Max)	I/P : 230 VAC O/P : FULL -MIN LOAD Ta : 25°C	V1 : 0.42 % ~ 0.42 %	P
6	SET UP TIME	230VAC : 2500 ms (Max) 115VAC : 2500 ms(Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC / 911 ms 115VAC / 1822 ms	P
7	RISE TIME	230VAC : 100 ms (Max) 115VAC : 100 ms (Max)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC / 10 ms 115VAC / 10 ms	P
8	HOLD UP TIME	230VAC : 50 ms (TYP) 115VAC : 20 ms (TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	230VAC / 59 ms 115VAC / 22 ms	P
9	OVER/UNDERSHOOT TEST	< ±5%	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	TEST : < 5 %	P
10	DYNAMIC LOAD	V1 : 1500 mVp-p	I/P : 230 VAC O/P : FULL /Min LOAD 90%DUTY/ 1KHZ Ta : 25°C	306 mVp-p	P

INPUT FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	INPUT VOLTAGE RANGE	85VAC~264 VAC	I/P : TESTING O/P : FULL LOAD Ta : 25°C	80 V~264V	P
			I/P : LOW-LINE -3V= 82 V HIGH-LINE+15%=300 V O/P : FULL/MIN LOAD ON : 30 Sec . OFF : 30 Sec 10MIN (AC POWER ON/OFF NO DAMAGE)	TEST : OK	
2	INPUT FREQUENCY RANGE	47HZ ~63 HZ NO DAMAGE OSC	I/P : 85 VAC ~ 264 VAC O/P : FULL -MIN LOAD Ta : 25°C	TEST : OK	P
3	POWER FACTOR	0.95 / 230 VAC(TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	PF= 0.97 / 230 VAC	P
		0.98 / 115 VAC(TYP)		PF= 1 / 115 VAC	
4	EFFICIENCY	88 % (TYP)	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	88.58 %	P
5	INPUT CURRENT	230V/ 0.6 A (TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I = 0.52 A/ 230 VAC	P
		115V/ 1.2 A (TYP)		I = 1.05 A/ 115 VAC	
6	INRUSH CURRENT	230V/ 65 A (TYP)	I/P : 230 VAC I/P : 115 VAC O/P : FULL LOAD Ta : 25°C	I = 32 A/ 230 VAC	P
		115V/ 35 A(TYP) COLD START		I = 16 A/ 115 VAC	
7	NO LOAD POWER CONSUMPTION	<0.5W	I/P : 240 VAC O/P : NO LOAD Ta : 25°C	0.35W	P
8	LEAKAGE CURRENT	< 300 uA/ for earth leakage current	I/P: 264 VAC O/P:Min LOAD Ta:25°C	L-FG 206 uA	P
		< 100 uA/ for touch leakage current		N-FG 206 uA	
				L-V+ 79 uA	
				L-V- 79 uA	
				N-V+ 79 uA	
				N-V- 79 uA	

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	OVER LOAD PROTECTION	105 %- 135 %	I/P : 230 VAC I/P : 115 VAC O/P : TESTING Ta : 25°C	129 %/ 230 VAC 129 %/ 115 VAC Constant current limiting for Vo=50 ~ 100% of rated voltage, recovers automatically after fault condition is removed	P
2	OVER VOLTAGE PROTECTION	CH1 : 18.8 V~ 21.8V	I/P : 230 VAC I/P : 115 VAC O/P : MIN LOAD Ta : 25°C	19.77 V/ 230 VAC 19.77 V/ 115 VAC Shut down Re- power ON	P
3	OVER TEMPERATURE PROTECTION (optional)	SPEC : TSW1 : 85 ± 5°C O.T.P. TSW1 : detect on heatsink Q101 of power transistor NO DAMAGE	I/P : 230 VAC O/P : FULL LOAD	O.T.P. Active Shut down o/p voltage · recovers automatically after temperature goes down	P
4	SHORT PROTECTION	SHORT EVERY OUTPUT 1 HOUR NO DAMAGE	I/P : 264 VAC O/P : FULL LOAD Ta : 25°C	NO DAMAGE Hiccup Mode	P

CONTROL FUNCTION TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	REMOTE CONTROL	Rc+ / Rc- 0 V- 0.8 V POWER ON 4 V- 10V POWER OFF	I/P : 230 VAC O/P : FULL LOAD Ta : 25°C	0 V-1.7 V POWER ON 1.8 V-10 V POWER OFF	P

COMPONENT STRESS TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	Power Transistor (D to S) or (C to E) Peak Voltage	Q 3 Rated : 2SK3673-01MR 10A/700V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2) Output Short (3)Full load continue Ta : 25°C	(1) 676 V (2) 552 V (3) 650 V	P
2	Diode Peak Voltage	Q101 Rated : STP80N10 80A/100V Q102 Rated : STP80N10 80A/100V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2)Output Short (3)Full load continue Ta : 25°C	(1) 99 V (2) 93.6 V (3) 70.8 V (1) 99 V (2) 93 V (3) 70 V	P
3	Clamp Diode Peak Voltage	D2 Rated : 3A/600V 1N5406	I/P : High-Line +3V = 267 V O/P : (1) Dynamic Load 90%Duty/1KHz (2)Full load continue Ta : 25°C	(1) 544 V (2) 552 V	P
4	Input Capacitor Voltage	C5 Rated : 100u/400V 105°C	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 380 V (2) 377 V (3) 399 V	P
5	Control IC Voltage Test	U1 Rated : PFC FAN6921MR 30V(max) 7.8V(min) U101 Rated : TEA1761T 38V(max) 8.35V(min)	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on /Off (2) Min load Turn on /Off (3)Full Load /Min load Change Ta : 25°C	(1) 22.81 V (2) 17.8 V (3) 23.1 V (1) 18.27 V (2) 12.85 V (3) 18.27 V	P
6	Power Transistor (D to S) or (C to E) Peak Voltage	Q1 Rated : 2SK4106 12A/500V	I/P : High-Line +3V = 267 V O/P : (1)Full Load Turn on (2) Output Short (3)Full load continue Ta : 25°C	(1) 460 V (2) 408 V (3) 440 V	P

SAFETY & E.M.C. TEST
SAFETY TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	WITHSTAND VOLTAGE	I/P-O/P: 4 KVAC/min I/P-FG: 2 KVAC/min O/P-FG: 0.5 KVAC/min	I/P-O/P: 4.2KVAC/min I/P-FG: 2.4KVAC/min O/P-FG: 0.6 KVAC/min Ta:25°C	I/P-O/P: 2.581 mA I/P-FG: 1.991 mA O/P-FG: 0.947 mA NO DAMAGE	P
2	ISOLATION RESISTANCE	I/P-O/P : 500VDC>100MΩ I/P-FG : 500VDC>100MΩ O/P-FG : 500VDC>100MΩ	I/P-O/P : 500 VDC I/P-FG : 500 VDC O/P-FG : 500 VDC Ta : 25°C /70%RH	I/P-O/P : 30 GΩ I/P-FG : 30 GΩ O/P-FG : 30 GΩ NO DAMAGE	P
3	GROUNDING CONTINUITY	FG(PE) TO CHASSIS OR TRACE < 100 mΩ	40 A / 2min Ta : 25°C / 70%RH	12 mΩ	P

E.M.C TEST

NO	TEST ITEM	SPECIFICATION	TEST CONDITION	RESULT	VERDICT
1	HARMONIC	EN61000-3-2 CLASS A CLASS D	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	PASS	P
2	CONDUCTION	EN55011 CLASS B	I/P: 230 VAC (50HZ) O/P:FULL/50% LOAD Ta:25°C	PASS Test by certified Lab	P
3	RADIATION	EN55011 CLASS B	I/P: 230 VAC (50HZ) O/P:FULL LOAD Ta:25°C	PASS Test by certified Lab	P
4	E.S.D	EN61000-4-2 INDUSTRY AIR:8KV / Contact:6KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
5	E.F.T	EN61000-4-4 INDUSTRY INPUT: 2KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
6	SURGE	IEC61000-4-5 INDUSTRY L-N :2KV L,N-PE:4KV	I/P: 230 VAC/50HZ O/P:FULL LOAD Ta:25°C	CRITERIA A	P
7	Test by certified Lab & Test Report Prepare				

7	THERMAL SHOCK TEST	1. Thermal shock Temperature : -40°C ~ +45°C 2. Temperature change rate : 25°C / MIN 3. Dwell time low and high temperature : 30 MIN/EACH 4. Total test cycle : 10 CYCLE 5. Input/Output condition : 230VAC/Full Load	OK	P
8	VIBRATION TEST	1 Carton & 1 Set (1) Waveform : Sine Wave (2) Frequency : 10-500Hz (3) Sweep Time : 12min/sweep cycle (4) Acceleration : 5G (5) Test Time : 60min in each axis (X.Y.Z) (6) Ta : 25°C	TEST : OK	P
9	CAPACITOR LIFE CYCLE	MSP-100-5: SUPPOSE C 105 IS THE MOST CRITICAL COMPONENT (1) I/P : 230VAC O/P : FULL LOAD Ta= 25 °C LIFE TIME (2) I/P : 230VAC O/P : FULL LOAD Ta= 40 °C LIFE TIME (3) I/P : 230VAC O/P : 75% LOAD Ta= 40 °C LIFE TIME	(1) 142932.7HRS (2) 46824.9HRS (3) 102498.6HRS	P
10	MTBF	MIL-HDBK-217F NOTICES2 PARTS COUNT TOTAL FAILURE RATE : 295.7K HRS		P

DATE	SAMPLE	TEST RESULT	TESTER	APPROVAL
2012/8/1	PRODUCT SAMPLE	PASS	SANFORD SU	VINCENT TSENG

2003/12/12 A50-F023